LBEV

(Shown with LBEV-UA Fitter and Ornamental Finial)

BEVERLY LANTERN - PLED

NOT TO SCALE

	Luminaire Schedule									
	Qty	Label	Arrangement	Description	LLF	Luminaire Lumens	Luminaire Watts	Total Watts	Mounting Height	UWLR	BUG Rating
A	1	LBEV-PLED-III-M-20LED-700mA-3_1	Single	LBEV-PLED-III-M-20LED-700mA-30K	0.850	4247	44	44	20	0.00	B1-U0-G1
B	9	LBEV-PLED-VSQ-W-20LED-700mA-3	Single	LBEV-PLED-VSQ-W-20LED-700mA-30K	0.850	4310	44	396	15, 20	0.00	B3-U0-G1
C	42	LBEV-PLED-IV-FT-20LED-700mA-3	Single	LBEV-PLED-IV-FT-20LED-700mA-30K-HS	0.850	3105	44	1892	15, 20	0.00	B0-U0-G1
D	13	LBEV-PLED-III-W-20LED-700mA-3	Single	LBEV-PLED-III-W-20LED-700mA-30K-HS	0.850	3107	44	572	15, 20	0.00	B0-U0-G1
E	3	LBEV-PLED-IV-FT-20LED-350mA-3	Single	LBEV-PLED-IV-FT-20LED-350mA-30K-HS	0.850	1745	22	66	15, 20	0.00	B0-U0-G1
F	1	LBEV-PLED-IV-20LED-350mA-30K-	Single	LBEV-PLED-IV-20LED-350mA-30K-HS	0.850	1857	22	22	15	0.00	B0-U0-G1
G	2	LBEV-PLED-III-W-20LED-350mA-3	Single	LBEV-PLED-III-W-20LED-350mA-30K-HS	0.850	1746	22	44	20	0.00	B0-U0-G1

MOUNTING HEIGHT IS "15' UNLESS NOTED OTHERWISE ON PLAN.

N

20 0 20 40 60

SCALE IN FEET

CBYD.COM 811 Call Before You Dig, Inc.

THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UTILITIES IN THE FIELD BEFORE BEGINNING ANY EXCAVATION. CALL AT LEAST 72 HOURS IN ADVANCE FROM ANYWHERE IN THE STATE OF CONNECTICUT, "CALL BEFORE YOU DIG": 1-800-922-4455

APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION ON _____ DATE
APPROVAL EXPIRES FIVE (5) YEARS FROM APPROVAL DATE

_____ _____
CHAIRMAN/SECRETARY DATE

REV.	DESCRIPTION OF REVISION	DATE	APPR.
1	PER STAFF TECHNICAL REVIEW COMMENTS	11/12/2024	GFA

STATE OF CONNECTICUT GEORGE F. ANDREWS JR. No. 18281 LICENSED PROFESSIONAL ENGINEER

Loureiro
Engineering Associates
Water • Facility Services • Laboratory
Loureiro Engineering Associates, Inc.
Consulting Engineers • Surveyors • Scientists
Groton, Connecticut 06340
Phone: 860-445-4939 Fax: 860-445-0999
An Employee Owned Company • www.Loureiro.com
©Loureiro Engineering Associates, Inc.
All Rights Reserved 2024

SCALE 1"=40'
COMM. NO. 06-HRC-4.01
DRAWN BY ESF DATE 11/12/2024
APPROVED BY GFA DATE 11/12/2024

PHOTOMETRIC AND LIGHTING PLAN

SHANTOK VILLAGE
1758 ROUTE 32, MONTVILLE, CT 06382

PREPARED FOR
1758 RTE 32, LLC
24 MAIN STREET, CENTERBROOK, CT 06409

DRAWING **E-1**

SHEET NO. 1 NO. OF SHEETS 1

V:\CT\MONTVILLE\ROUTE 32-1758\1758 RTE 32, LLC - 06-HRC-4.01\DWGS\CTV1\PHOTOMETRIC AND LIGHTING PLAN.DWG Tab: PHOTOMETRIC AND LIGHTING PLAN Saved: 11/12/2024 1:46 PM by ESFARMER Plotted: 11/12/2024 1:47 PM